

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/24/2017-18, Date: 21.02.2018

Improvements to Roads and Drains at Chamundeshwari Layout in Ward No. 10 (Doddabommasandra), Vidyanarayana Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				ASWATHNARAYAN ANJANAPPA	
				In Figures	In Words
1	309	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work.	Cum	185.12	Rupees One Hundred Eighty Five and Twelve Paise Only
2	49.95	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work.	Cum	4450	Rupees Four Thousand Four Hundred Fifty Only
3	104.9	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams etc complete as per specifications and directions of engineer in charge of the work.	Cum	5340	Rupees Five Thousand Three Hundred Forty Only
4	6.29	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery etc complete as per specifications and directions of engineer in charge of the work.	Tonne	63465.9	Rupees Sixty Three Thousand Four Hundred Sixty Five and Ninety Paise Only
5	799.2	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work.	Sqm	306.16	Rupees Three Hundred Six and Sixteen Paise Only
6	299.7	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete 7.5 cms thick etc complete as per specifications and directions of engineer in charge of the work.	Sqm	656.82	Rupees Six Hundred Fifty Six and Eighty Two Paise Only
7	1665	Providing chamfering edges to stone slab 2.5cms. wide as per specifications. (only chamfered length shall be recorded) etc complete as per specifications and directions of engineer in charge of the work.	m	36.49	Rupees Thirty Six and Forty Nine Paise Only
8	299.7	Providing two line dressing to granite stone slab / granite stone masonry etc complete as per specifications and directions of engineer in charge of the work	Sqm	951.41	Rupees Nine Hundred Fifty One and Forty One Paise Only
9	9.99	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5696.89	Rupees Five Thousand Six Hundred Ninety Six and Eighty Nine Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92